ATLANTIC OCEAN

STA. 1+41 (R-101) - AZ 101°

STA. 5+99 (CSI-102.5) - AZ 101°

STA. 10+61 (R-103) - AZ 92°

MATCH LINE A
SHEET CM-2

SCALE IN FEET
1" = 50'
25 0 50

NEARSHORE SEAGRASS BOUNDARY (AUG. 2010), TYP.

APPROX. LANDWARD LIMIT OF CONSTRUCTION BERM

SEAWARD TOE OF BEACH FILL CONSTRUCTION

SEAWARD EDGE OF BERM +5.5' NAVD

POB
STATION=0+00.0
NORTHING=497122.0
EASTING=934132.6

0+00 1+00 2+00 3+00 4+00 5+00 6+00 7+00 8+00 9+00 10+00 11+00 12+00 13+00 14+00 15+00

R-102

CSI-102.5

ECL

R-103

POL-1
STATION=10+54.8
NORTHING=496087.9
EASTING=933924.4

CONSTRUCTION ACCESS

ISLAND HOUSE

KEY COLONY

SILVER SANDS

CCCL

LEGEND

- PROPOSED BEACH FILL
- CSI-102.5 CSI REFERENCE HALF MONUMENT
- R-107 DEP REFERENCE MONUMENT
- SLOPE DIRECTION
- ECL
- CCCL
- -15- CONTOUR
- SEAGRASS BOUNDARY (AUG. 2010)
- CONSTRUCTION BASELINE

NOTES

1. REFER TO SHEET G-2 FOR SURVEY AND GENERAL NOTES INFORMATION.
2. REFER TO SHEETS CM-5 TO CM-8 FOR SECTIONS.

NOTE:
ALL SCALES INDICATED PERTAIN TO FULL SIZE DRAWINGS (24"x36")

F:\Project\135040.02\Construction Drawings\Working\135040.02-CM-PLAN.dwg

KEY BISCAYNE BEACH RENOURISHMENT PROJECT

VILLAGE OF KEY BISCAYNE
FLORIDA

COASTAL SYSTEMS INTERNATIONAL, INC.
464 South Dixie Highway
Coral Gables, Florida 33146
Tel: 305-661-3655
Fax: 305-661-1914
www.CoastalSystemsInt.com
State of Florida EB #7087
Coastal, Environmental,
Civil Engineering and Management

CONSULTANTS

THESE PLANS ARE IN COMPLIANCE WITH THE APPLICABLE SECTIONS OF 62B-41, F.A.C.

ISSUE	DATE	DESCRIPTION
.	04-30-12	100% SUBMITTAL

PROJECT NO: 135040.02
DATUM: NAVD
DRAWN BY: VC
CHECKED BY: TKB

ENGINEER OF RECORD

DRAWING NOT VALID WITHOUT EMBOSSED SEAL

T.K. BLANKENSHIP
FL.REG.55910

BEACH FILL PLAN STA. 0+00 - 15+00

CM-1

6 OF 13 SHEETS